

Innovating with Segmental Caisson Construction to Build a New Pump Station in Wellington's CBD

Callum Allison – GHD Ltd
Caroline Anderson - Brian Perry Civil

Asset Owner – Wellington City Council
Client – Wellington Water
Designer – GHD Ltd
Contractor – Brian Perry Civil




Absolutely Positively
Wellington City Council
Me Heke Ki Pōneke



Contents

- The Need
- Extent of Works
- Challenging the Conventional Approach
- Seismic Loading
- Complex Site Constraints
- Delivering Construction
 - Contaminated Water
 - Groundwater Drawdown Risk



The Need

Customer Outcomes

Safe & Healthy Water


 Protect public from untreated spills to ocean

Respectful of the environment

 Ensure water services in built environment comply with consents and unintrusive

Resilient networks support the economy

 Provide customers access to reliable wastewater services

 Provide wastewater networks that are resilient to shocks and stresses

 Plan to meet future growth and manage demand



CHALLENGES

Smart cities rely on **smart solutions** to thrive and grow.


LOCATION?

- Existing sewer network at full capacity
- 65,000 pop. increase (30y)
- 7300 new CBD dwellings
- New Pump Station preferred solution to permit growth in the CBD**
- First new PS for 40 years
- Reduce overflow spills to harbour

Symbol	Address	No. of Apartments
	111 Dixon Street	114
	160 Victoria Street	86+
	166 Victoria Street	146

Developments to be constructed by 2021


Extent of design




Analysis Basis	Average Dry Weather Flow ADWF (L/s)	Peak Dry Weather Flow PDWF (L/s)	Peak Wet Weather Flow PWWF (L/s)
2018 Flows	4.9	25.1	26.1
Fully Developed Flows	15.3	71.9	72.9

- PWWF – 73 l/s
- Below ground structure, 8m deep
- Divert 2 catchments
- Pipework
 - 60m x 300mm PE gravity
 - 170m x 250mm PE pressure
- Connect to interceptor gravity sewer
- Emergency Overflow weir structure

Challenging the Conventional



- Limited site locations and associated space
- Traditional approach
 - Cast in-situ – sheet piled excavation (or similar)
 - Cast on-site standard caisson structure
- Initial design – 7.8 x 5.2 x 6 m (d) concrete box



- Initial Construction Review Issues
 - Installation Noise / Vibration
 - Close proximity to roads, buildings and pedestrians



Tender Innovation Sought

- Potential benefits of Precast Concrete Segmental Caisson

Common in Europe
 Quicker installation
 Safer – deep excavations
 Quieter
 Reduced footprint

- Complexities in New Zealand

Segment availability
 Seismic performance
 NZ Design Standards



- 1m deep precast concrete segments
- Joined to form rings
- Excavate from inside
- Hydraulic jack assisted


© FP McCann – Precast Tunnel & Shaft Solutions

Tender Innovation sought

- Potential benefits of Precast Concrete Segmental Caisson



- Complexities in New Zealand



- Successful Contractor Methodology




- Perfect for site constraints
- Preserve pedestrian and vehicle access
- Reduce disruption to businesses
- Retain existing urban streetscape and vegetation




- 6.5m dia not available in NZ
- Shipped direct from UK

Internal Walls – Seismic Loading – Critical Asset

- Wetwell / dry well configuration
- Internal wall design to NZ Building Code
- Fire assessment
- Access and egress
- 3D Model brought design to life




- Water retaining structure
- Importance Level 4
- 100y durability
- 1 in 2500y ULS event
- Internal walls




Internal Walls – Seismic Loading – Critical Asset

- Wetwell / dry well configuration
- Internal wall design to NZ Building Code
- Fire assessment
- Access and egress
- 3D Model brought design to life





- Water retaining structure
- Importance Level 4
- 100y durability
- 1 in 2500y ULS event
- Internal walls



- Seismic model assessment by contractor sub-consultant
 - Connections of internal walls and their effect on segments
 - Continuous wall (full height)
 - Movement of individual segments
 - Maximum limit of joint displacement

Challenging Site Constraints



- Small site footprint
- Shallow Foundation buildings (5m)
- Live road (1m)
- Existing trees
- Consents
 - Contaminated Land
 - Dewatering Consent
 - Building Consent
- Noise Management

Rising Main and Gravity Pipeline Construction



- Horizontal Directional drilling of rising main
- Traffic management in Wellington CBD
- Construction site loading zone



Site Establishment



- Service Diversions
 - Storm water
 - HV Power
 - Telecom
- Tree
 - Moved PS 300mm further away
- Streetlight
- Traffic Management
- Pedestrian Safety

Cutter Ring



- Precast segments
- 10 segments = 1 ring
- Taper on cutter ring
- Shear Key for concrete base plug

First Standard Ring



Construction of Reinforced Concrete Collar



Collar Benefits:

- Trench support
- Reaction mass for Hydraulic Jacks
- Vertical Guide
- Anti-flotation structural mass

Caisson Build, Excavation and Sinking



- 24t “no swing” excavator
- Sandy Silt
- Spoil transferred to trucks on road

Caisson Build, Excavation and Sinking



- Custom-made Clamshell Bucket
- Caution working around tree
- Groundwater reached (4.5m BGL)



Connecting Segments





PORT-MOM
Building Solutions

W
PY

PLEHRE
0800HRE T

PLEHRE



Formation level reached

- 7 Rings in 21 days
- 7.8m deep
- 700t soil excavated





Caisson concrete base plug and dewatering





- Managing contaminated groundwater
 - Hydrocarbons > Trade Waste Consent limit
 - No discharge to sewer permitted
 - Mobilised 3 x 40m³ storage tanks
 - Time to settle before discharge
 - Significant cost implications
- Groundwater drawdown risk to surrounding buildings



Concrete base plug – Groundwater drawdown & risk of settlement in buildings



Concrete base plug – Groundwater drawdown & risk of settlement in buildings




Concrete base plug – Groundwater drawdown & risk of settlement in buildings




Concrete base plug – Groundwater drawdown & risk of settlement in buildings


A




Stage	Total Time	Comment
A	0 mins	-> Pump started at 2.0 l/s to monitor initial water level changes
A – B	60 mins	-> No significant change, therefore pump increased to max output of 5.7 l/s
B – C	120 mins	-> 50% target water level in caisson -> BH water sensor level tracking above estimated drawdown profile, no risk of settlement -> Tracking line of water levels in BH v's caisson were diverging which increased confidence -> Confirmed safe to proceed with 56m ³ concrete delivery to complete base plug installation
D	160 mins	-> Pump failure, switched over to standby pump
E	220 mins	-> Target water level in caisson reached -> BH water sensor level remained above alarm level 1 confirming no risk of settlement




Concrete base plug – Groundwater drawdown & risk of settlement in buildings




Stage	Total Time	Comment
A	0 mins	-> Pump started at 2.0 l/s to monitor initial water level changes
A – B	60 mins	-> No significant change, therefore pump increased to max output of 5.7 l/s
B – C	120 mins	-> 50% target water level in caisson -> BH water sensor level tracking above estimated drawdown profile, no risk of settlement -> Tracking line of water levels in BH v's caisson were diverging which increased confidence -> Confirmed safe to proceed with 56m ³ concrete delivery to complete base plug installation
D	160 mins	-> Pump failure, switched over to standby pump
E	220 mins	-> Target water level in caisson reached -> BH water sensor level remained above alarm level 1 confirming no risk of settlement




Concrete base plug – Groundwater drawdown & risk of settlement in buildings




Stage	Total Time	Comment
A	0 mins	-> Pump started at 2.0 l/s to monitor initial water level changes
A – B	60 mins	-> No significant change, therefore pump increased to max output of 5.7 l/s
B – C	120 mins	-> 50% target water level in caisson -> BH water sensor level tracking above estimated drawdown profile, no risk of settlement -> Tracking line of water levels in BH v's caisson were diverging which increased confidence -> Confirmed safe to proceed with 56m ³ concrete delivery to complete base plug installation
D	160 mins	-> Pump failure, switched over to standby pump
E	220 mins	-> Target water level in caisson reached -> BH water sensor level remained above alarm level 1 confirming no risk of settlement



Concrete base plug – Groundwater drawdown & risk of settlement in buildings



Stage	Total Time	Comment
A	0 mins	-> Pump started at 2.0 l/s to monitor initial water level changes
A – B	60 mins	-> No significant change, therefore pump increased to max output of 5.7 l/s
B – C	120 mins	-> 50% target water level in caisson -> BH water sensor level tracking above estimated drawdown profile, no risk of settlement -> Tracking line of water levels in BH v's caisson were diverging which increased confidence -> Confirmed safe to proceed with 56m ³ concrete delivery to complete base plug installation
D	160 mins	-> Pump failure, switched over to standby pump
E	220 mins	-> Target water level in caisson reached -> BH water sensor level remained above alarm level 1 confirming no risk of settlement



Internal Floor and Walls



- First time workers enter the Caisson
- Wall connections
- Reinforced floor slab

Internal dividing walls



- Separation for wet and dry well
- Pre-cast wall panels
- Connection design for cast in-situ
- 100t mobile crane for lift

Structural Floor and Mechanical fit out



- Mezzanine floor supported off precast corbel
- Pumps and pipework installation
- Electrical control board installation



Precast corbel support sections

Precast Concrete Roof Slab Placement



- 400mm thick slab
- 100t mobile crane
- 18.5t load
- 2 week programme saving

Reinstatement



Completed internal fit out of dry well



Reinstatement – hidden out of sight

- Custom made lift assist access cover
- Extendable handrails



- Paver infill access covers



What did we find

- What we were looking for
 - Quicker construction
 - Safer working environment
 - Reduced noise
 - Smaller footprint
 - Minimised disruption
- Contaminated ground / water biggest challenge
 - Correct methodology
 - Real time data
- Collaboration is key to safe and successful delivery
 - Pre-construction design stage
 - Geo / Str Eng input critical
- Unique in NZ (as far as we know)
 - Innovative integral internal wall design
 - Inside a precast segmental water retaining structure





Thank you – Questions?



Absolutely Positively
Wellington City Council

Me Heke Ki Pōneke



**INNOVATIVE SEGMENTAL CAISSON CONSTRUCTION
FOR A NEW PUMP STATION IN WELLINGTON'S CBD**